

12. FINISHING AND REPAIR

- 12.1 DO NOT TROWEL WITH BLEED WATER PRESENT OR IN RAIN. ROOF SLABS SHALL NOT BE STEEL-TROWELLED SMOOTH U.N.O. [EIT 011014 11.2]
- 12.2 HONEYCOMB AND DEFECTS ARE REPAIRED ONLY BY AN APPROVED METHOD: CUT BACK TO SOUND CONCRETE, WET, REPAIR WITH APPROVED MORTAR OR CONCRETE. STRUCTURAL DEFECTS PER THE ENGINEER. [EIT 011014 11.3]

13. INSPECTION AND RECORDS

- 13.1 KEEP RECORDS OF MATERIALS, MIXES, DELIVERY TICKETS, POURS (DATE, TIME, LOCATION, VOLUME, WEATHER), TESTS, CURING, FORMWORK AND SHORING, REINFORCEMENT APPROVALS, CONSTRUCTION LOADS, DEVIATIONS AND PHOTOGRAPHS; RETAIN ≥ 2 YEARS AFTER COMPLETION. [EIT 011008 1.3.2 – 1.3.4, 3.1.2; EIT 011014 13.1]
- 13.2 INSPECT COMPLETED MEMBERS; REPAIR DEFECTS AS INSTRUCTED BEFORE THE STRUCTURE IS USED. [EIT 011014 12.5.1]

14. FOUNDATIONS AND PILES

- 14.1 DESIGN BASED ON THE SOIL INVESTIGATION REPORT [REF., DATE]. SPREAD FOOTINGS: ALLOWABLE BEARING [] t/m² AT [] m BELOW GROUND; PILES: TYPE [], SIZE [], SAFE LOAD [] t / PILE, TIP LEVEL [].
- 14.2 PILE TESTS: [STATIC / DYNAMIC] LOAD TEST ON [] PILES AND INTEGRITY TEST ON [] % OF THE PILES; RESULTS TO THE ENGINEER BEFORE THE CAPS ARE CAST.
- 14.3 PILE POSITION AND PLUMBNESS WITHIN THE SPECIFIED TOLERANCES; PILES OUT OF TOLERANCE, DAMAGED OR SHORT ARE REPORTED TO THE ENGINEER BEFORE THE CAP IS FORMED.
- 14.4 PILE HEADS CUT TO SOUND CONCRETE; PILE EMBEDMENT AND ANCHORAGE INTO THE CAP PER THE FOUNDATION DETAILS. CAP BOTTOM BARS CLEAR ABOVE THE PILE HEADS.
- 14.5 LEAN CONCRETE 50 UNDER FOOTINGS, CAPS AND GROUND BEAMS. EXCAVATIONS KEPT DRY; DEWATERING AND SHORING DESIGNED BY THE CONTRACTOR. FILL UNDER SLABS ON GROUND COMPACTED IN LAYERS TO THE SPECIFIED DENSITY.

ABBREVIATIONS

GENERAL	
DB, RB	DEFORMED BAR, ROUND BAR
f'c, f'cr	SPECIFIED CYLINDER STRENGTH, REQUIRED MEAN STRENGTH
fy	YIELD STRENGTH OF REINFORCEMENT
w/b, w/cm	WATER-BINDER RATIO
ss	STANDARD DEVIATION OF STRENGTH TESTS
ksc	kg/cm² (1 MPa ≈ 10.2 ksc)
TYP., SIM.	TYPICAL, SIMILAR
U.N.O.	UNLESS NOTED OTHERWISE
N.T.S.	NOT TO SCALE
C/C, CLR.	CENTRE TO CENTRE, CLEAR
CL	CENTRE LINE
THK., DIA., Ø	THICKNESS, DIAMETER
MIN., MAX.	MINIMUM, MAXIMUM
EL., FFL, SFL	LEVEL; FINISHED / STRUCTURAL FLOOR LEVEL
CJ, EJ	CONSTRUCTION JOINT, EXPANSION JOINT
SOG	SLAB ON GROUND
EIT 011008	EIT STANDARD 011008-21 (DESIGN)
EIT 011014	EIT STANDARD 011014-19 (MATERIALS AND CONSTRUCTION)
DPT	DEPARTMENT OF PUBLIC WORKS AND TOWN & COUNTRY PLANNING STANDARD


REBAR POSITION AND BAR CALL-OUTS

n-DBxx	n BARS OF DIAMETER xx mm, e.g. 4-DB20
DBxx @ s	BARS OF DIAMETER xx mm AT s mm CENTRES, e.g. DB12 @ 200
T, B	TOP, BOTTOM
T1, T2	TOP BARS: OUTER LAYER, SECOND LAYER
B1, B2	BOTTOM BARS: OUTER LAYER, SECOND LAYER
EF	EACH FACE
NF, FF	NEAR FACE, FAR FACE
IF, OF	INNER FACE, OUTER FACE (WALLS, TANKS)
EW	EACH WAY
ES	EACH SIDE
ADD.	ADDITIONAL BARS (ADDED TO THE CONTINUOUS BARS)
CONT.	CONTINUOUS
ALT.	ALTERNATE (ALTERNATE BARS / HOOKS)
STR., TIE	STIRRUP (BEAMS), TIE (COLUMNS); HOOP = CLOSED TIE WITH SEISMIC HOOKS


SYMBOLS IN THE DETAILS

ℓn	CLEAR SPAN, FACE TO FACE OF SUPPORTS
L1, L2	SPANS OF ADJACENT BAYS, AS DIMENSIONED
Lc	CANTILEVER LENGTH FROM THE SUPPORT FACE
Sn	CLEAR SHORT SPAN OF A SLAB PANEL
h	OVERALL DEPTH OF A BEAM; THICKNESS OF A SLAB
d	EFFECTIVE DEPTH
bw	WEB WIDTH OF A BEAM
c	CLEAR COVER (TABLE 7)
c1, c2	COLUMN SIZE IN, ACROSS THE SPAN DIRECTION
Hc	CLEAR HEIGHT OF A COLUMN
lo	LENGTH OF THE COLUMN END ZONE (CONFINEMENT)
s	SPACING OF BARS, TIES OR STIRRUPS
s0, s1	TIE SPACING IN THE COLUMN END ZONE; STIRRUP SPACING IN THE BEAM 2h ZONE
hx	MAX. CENTRE SPACING OF HOOP LEGS OR CROSSTIES
db, dt	DIAMETER OF THE MAIN BAR, OF THE TIE OR STIRRUP
Ld, ldh	DEVELOPMENT LENGTH, STRAIGHT / HOOKED (TABLE 6)


TYPICAL COVER - BEAM SECTION



STANDARD HOOKS



TYPICAL LAP SPLICES - STAGGER



NOTES

1. APPLIES TO ALL STRUCTURAL DRAWINGS.
2. DIMENSIONS IN mm; LEVELS IN m.
3. DO NOT SCALE FROM DRAWINGS.
4. DRAFTING TO EIT 011006-19.

ISSUED FOR USE

KEY PLAN (N.T.S.)

NOT APPLICABLE
(GENERAL NOTES)

REVISIONS

REV	DESCRIPTION	DATE	SIGN
A	ISSUED FOR USE	03/10/2026	

OWNER / CLIENT APPROVAL

SIGNATURE :
NAME : DATE :

LOCAL AUTHORITY (BUILDING CONTROL)

PERMIT NO. :
[STAMP]

OWNER

[OWNER NAME]

PROJECT

[PROJECT NAME]
[BUILDING / LOCATION]

STRUCTURAL DESIGN OFFICE

[DESIGN OFFICE NAME]
[ADDRESS / TEL. / E-MAIL]

DRAWING TITLE

GENERAL NOTES (3)
STRUCTURAL CONCRETE

DESIGNED :	DRAWING NO. STR-ST-1003-F-A	
DRAWN :	SHEET 3 OF 3 A3	
CHECKED :		
ENGINEER :		
COE LICENSE NO. :	SCALE N.T.S.	DATE 03/10/2026
SIGNATURE :		

APPROVED BY : DATE :